Proprietary to General Electric Company

New Tube Configure

(Click Here for Summary Version)

1 Personnel Requirements

Required Persons	Preliminary Reqs	Procedure	Finalization
1	4 mins	10 mins	Not Applicable

2 Overview

Last Revised:	03/16/04

3 Preliminary Requirements

3.1 Required Conditions

Condition	Reference	Effectivity
Procedure should only be run after a new tube has been installed.	-	-

4 Procedure

1. Run [NEW TUBE CONFIG] program.
2. Enter the failure codes and new values.
3. Exit.
    - The console will reboot after performing this operation.
    - The system will set the tube temperature to hot, after configuring a new tube. The cooling delay is approximately 90 minutes.

5 Finalization

No finalization steps.

Back to top